

Field Test Procedure (Water & Structural)

Field tests are to be performed per AAMA 502 and performed "on newly installed fenestration product(s)" as required in paragraph one of Short Form Field Testing Specifications.

All labeled FLEETWOOD doors and windows will be manufactured in precisely the same manner as the approved test specimen or as stated on the order. Expect only 75% of laboratory performance results in typical field installation conditions.

The requirements herein supersede all other documents, including plans and specifications.

I. Installation

- 1. The FLEETWOOD product must be installed according to the FLEETWOOD **Installation Instructions** and all **Federal, State and Local Codes** and **Regulations**.
- 2. If the product is not installed plumb, level and square the test cannot be performed until the product is properly installed.
- 3. Testing must be performed during the first 10% of installation and within four (4) weeks of installation.

II. Testing Credentials & Instrument Verification

1. Field tests are to be performed by a testing laboratory accredited to ISO/IEC 17025.

III. Factory Field Participation

- 1. Before any testing is commenced, Fleetwood requires the proper forms to be submitted by an Authorized Fleetwood Dealer. Upon acceptance, Fleetwood requires 30 days to schedule availability of an exact date.
- 2. The Authorized Dealer will submit copies of the following: (prior to the 30 days commencing)
 - a. The intended test plan
 - b. The Fleetwood Order indicating the Fleetwood Products purchased
 - c. The Installer of the products tested and their credentials
- 3. The Authorized Dealer agrees to cover all expenses of factory participation e.g. travel, lodging and labor.
- 4. At Fleetwood's discretion, remediation will be allowed to correct minor fabrication/installation faults of a non-structural nature which cause the failure. If remediation is required, testing shall begin again, after remediation is performed, at the beginning of the test where the failure occurred.
- 5. FLEETWOOD will not be financially responsible for any field testing, regardless of pass or failure.